


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Morton County, Sec. 23 Twp. 31S Rge. 43 (X) (W)
Location as "NE/CNW/SW" or footage from lines C NE
Lease Owner Thomas & Brewer - Alamo Corp.
Lease Name Orr Well No. 1
Office Address Box 985, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 11, 19 57
Application for plugging filed May 11, 19 57
Application for plugging approved May 11, 19 57
Plugging commenced May 11, 19 57
Plugging completed May 11, 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5240 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 1478' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 650', set plug at 650'

Pumped 35 sacks on plug through pipe (with Halliburton pump truck)

filled to 35' with mud, set tied plug at 35', filled to

bottom of cellar with 15 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwestern Drilling Company
Address 303 South Virginia, Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
Lloyd Henderson (employee of owner) XXXXXXXXXXXXXX of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lloyd Henderson

Box 985, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 57

My commission expires March 30, 1961

RECEIVED Notary Public.
STATE CORPORATION COMMISSION

MAY 17 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 24 T 31 2 43W
BOOK PAGE 12 16

ORR NO. 1

NE/4 Section 23-31S-43W
Morton County, Kansas
Alamo Corporation

8-5/8" O. D. casing cemented at 1476'

Drilling commenced April 18, 1957
Drilling completed May 11, 1957

| FROM | TO | FORMATION | REMARKS |
|------|------|-------------------------|---|
| 0' | 40' | Sand & clay | |
| 40 | 270 | Sand, clay & shells | |
| 270 | 450 | Sandy clay | |
| 450 | 524 | Red clay & shale | |
| 524 | 636 | Shale & gyp | |
| 636 | 995 | Anhydrite & red bed | |
| 995 | 1015 | Sand | |
| 1015 | 1064 | Anhydrite & red bed | |
| 1064 | 1100 | Anhydrite | |
| 1100 | 1320 | Red bed & anhydrite | |
| 1320 | 1395 | Anhydrite & red bed | |
| 1395 | 1450 | Shale & gyp | |
| 1450 | 1465 | Shale & anhydrite | |
| 1465 | 1518 | Anhydrite | |
| 1518 | 1855 | Red bed & sand | 8-5/8" O. D. casing cemented with 750 sacks cement at 1476' |
| 1855 | 2275 | Red bed, shale & shells | |
| 2275 | 2818 | Lime & shale | |
| 2818 | 2965 | Shale & lime | |
| 2965 | 3094 | Lime & shale | |
| 3094 | 3220 | Lime | |
| 3220 | 3340 | Lime & shale | |
| 3340 | 3419 | Shale & lime | |
| 3419 | 3802 | Lime & shale | |
| 3802 | 3873 | Lime | |
| 3873 | 4007 | Lime & shale | |
| 4007 | 4065 | Lime | |
| 4065 | 4477 | Lime & shale | |
| 4477 | 4518 | Lime | |
| 4518 | 4555 | Lime & shale | |
| 4555 | 4593 | Lime | |
| 4593 | 4720 | Lime & shale | |
| 4720 | 4785 | Shale & lime | |
| 4785 | 4861 | Shale & lime streaks | |
| 4861 | 4980 | Shale & lime | |
| 4980 | 5030 | Shale & pyrite | |

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 X 1957

CONSERVATION DIVISION
Wichita, Kansas

| | | | |
|----------|------|------|-----|
| PLUGGING | | | |
| FILE | SEC | T | 43W |
| BOOK | PAGE | LINE | 16 |
| | | | |

| FROM | TO | FORMATION | REMARKS |
|------|-------|--------------|--------------|
| 5030 | 5060 | Sand & shale | |
| 5060 | 5156 | Shale & sand | |
| 5156 | 5225 | Sand | |
| 5225 | 5240 | Lime & shale | Well plugged |
| T.D. | 5240' | | |

This is a true copy of the driller's log as shown on the drilling tickets.

BARBOUR DRILLING COMPANY

By: *J. M. Barbour*

Subscribed and sworn to before me on this 20th day of May, 1957.

Edward W. Dibley
Notary Public

My commission expires: July 1, 1957