


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plot

Rush County, Sec. 31 Twp. 19 Rge. 19 (E) (W) X  
Location as "NE/CNW&SW&" or footage from lines C/NE/NW  
Lease Owner Mull Drilling Co.  
Lease Name WEST Well No. 3  
Office Address 415 Page Court, 220 W. Douglas, Wichita, Ks. 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 5, 1975  
Plugging completed November 11, 1975  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4250 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	370	-0-
				4 1/2	4249	2326.30'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged bottom back to 4175' with sand and 3 sacks cement. Shot casing at 2810 and 2330'. Pulled a total of 73 joints of 4 1/2" casing. Allied squeezed well with 20 sacks gel, 3 sacks hulls, 100 sacks cement, 5 sacks gel and 20 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rockhold Engineering, Inc.  
Address P. O. Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton  
James W. Rockhold (employee of owner) or (Notary Public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 698, Great Bend, Kansas 67530

(Address)

9th day of November 1975

Cathy Peacock


Cathy Peacock

Notary Public.

My commission expires September 30, 1979

RECEIVED  
STATE CORPORATION COMMISSION

NOV 20 1975  
11-20-75  
CONSERVATION DIVISION  
Wichita, Kansas



WEST #3

LOCATION:	C NE/4 NW/4 Section 31-19S-19W Rush County, Kansas	DATE SPUDDED: 4-14-62 ROTARY COMPLETION: 4-23-62
OPERATOR:	MULL DRILLING CO., INC.	ELEVATION: 2246 GL 2249 DF 2251 KB
CONTRACTOR:	Walters Drilling Co.	
SURFACE CASING:	8-5/8" set @ 370' with 185 sacks cement	
OIL STRING:	4-1/2" set @ 4249' with 125 sacks cement	

L O G  
(Figures indicate bottom of formation)

Shale	0-370'
Shale & Shells	635'
Red Bed & Shale	700'
Shale & Shells	830'
Sand	1040'
Shale & Shells	1410'
Anhydrite	1440'
Shale & Shells	2020'
Shale	2265'
Lime	2870'
Shale & Lime	3830'
Lime	4097'
Lime & Shale	4206'
Sand & Shale	4250'
Total Depth	4250'

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By Robert F. Walters  
ROBERT F. WALTERS, Partner

Subscribed and sworn to before me  
this 26th day of April, 1962

R. L. Abel  
R. L. Abel, Notary Public

My commission expires January 4th, 1964

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 19 1975  
11-19-75  
CONSERVATION DIVISION  
Wichita, Kansas