


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plot

Rush County, Sec. 36 Twp. 19S Rge. 20W (EX) (XX)  
Location as "NE/CNW&SW" or footage from lines. NE SW SW  
Lease Owner The National Oil Company  
Lease Name V. Smith Well No. 1  
Office Address Suite 550, O.W. Garvey Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 7, 1972  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced December 7, 1972  
Plugging completed December 7, 1972  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation Depth to top Bottom Total Depth of Well 3,800 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 316'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,800 feet (rotary total depth) to 660 feet.  
Set plug at 660 feet and cemented with 70 sacks cement.  
Filled hole with heavy rotary mud from 660 feet to 300 feet.  
Set plug at 300 feet and cemented with 20 sacks cement.  
Filled hole with heavy rotary mud from 300 feet to 40 feet.  
Set solid plug at 40 feet and cemented to cellar with 10 sacks cement, two sacks cement in rathole.  
Plugging operations accomplished utilizing Halliburton Oilwell Cementing pump truck through 4 1/2 inch drill pipe.


RECEIVED  
STATE CORPORATION COMMISSION  
12-14-72  
DEC 14 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor H-30, Inc.  
Address 200 No. Main, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.  
Dean Britting, Agent (Signature of owner) or (Signature of operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 No. Main, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 13th day of December, 1972  
Elsie Willison  
My commission expires June 30, 1974  
Notary Public.



15-165-20450-0000  
KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY The National Oil Company

SEC. 36 T. 19 R. 20W  
LOC. NE SW SW

FARM V. Smith

NO. 1

TOTAL DEPTH 3,800'

COMM. December 1, 1972

COMP. December 7, 1972


SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED

COUNTY Rush

KANSAS



CASING

20

10

15

8

12

6

13

5

-5/8" 316' cemented w/185 sxs cement ELEVATION 2,276 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shells and Shale  
Shale and Shells  
Shale and Red Bed  
Sand  
Shale  
Anhydrite  
Shells and Shale  
Shale and Lime  
Lime and Shale  
Rotary Total Depth

336'  
450'  
850'  
1,045'  
1,427'  
1,462'  
1,734'  
2,400'  
3,800'  
3,800'

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1972  
12-14-72  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above and foregoing  
to be a true and correct log of the above  
described well as shown by the drilling  
reports.

H-30, INC.

Dean Britting  
Dean Britting

State of Kansas

County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary  
Public in and for said county and state  
this 13th. day of December, 1972.

Elsie Wilkinson  
Elsie Wilkinson - Notary Public

My Commission Expires:

June 30, 1974

