


15-165-0093-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rush County. Sec. 6 Twp. 19 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Woodman & Iannitti Drilling Company
Lease Name Pozalek Well No. 1
Office Address Box 387, Hoisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-2-1957
Application for plugging filed 3-2-1957
Application for plugging approved 3-2-1957
Plugging commenced 3-2-1957
Plugging completed 3-2-1957
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4007 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	308'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud, 1/3 sack hulls, plug at 410, rock bridge 395, 60 sacks cement with pump truck. Heavy mud, 1/3 sack hulls plug 20', 5 sacks.

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 - 1957
3-6-57
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Woodman & Iannitti Drilling Co.
Address P. O. Box 387, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman
717 Union National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 1957

Lucille L. Harrington
Notary Public.

My commission expires November 30, 1959

PLUGGING
FILE SEC 6 T 19 R 17W
BOOK PAGE 144 LINE 45

15-165-0093-0000

DRILLING LOG

Company: Woodman and Iannitti Drilling Co. and Frank A. Oyster
 Lease: Pozalek
 Well: #1 Pozalek NW NW SE 6-19-17, Rush County, Kansas
 Contractor: Woodman and Iannitti Drilling Co.
 P. O. Box 387, Hoisington, Kansas
 Date Comm: 2-18-57
 Date Compl: 3-2-57
 T. D.: 4007'
 Casing: 308' 8 5/8" surface casing

Figures Indicate the Bottom of Formation

0-160	Shale & Shells	2540	Lime & Shale
226	Shale & Shells	2595	Shale & Lime Shells
308	Red Bed & Shale	2655	Shale & Lime Shells
325	Red Bed & Shale	2750	Shale & Lime Shells
362	Sand	2840	Shale & Lime
570	Shale & Shells	2930	Shale & Shells
590	Shale	2989	Shale & Shells
755	Dakota Sand	3055	Lime & Shale
775	Shale	3190	Lime & Shale
815	Sand	3265	Lime & Shale
1207	Red Bed & Shale	3310	Lime & Shale
1220	Anhydrite	3490	Shale & Shells
1240	Anhydrite	3530	Lime
1485	Red Bed & Shale	3560	Lime
1532	Red Bed & Shale	3620	Lime
1865	Shale	3652	Lime
1945	Brown Lime & Shale	3705	Lime
2045	Brown Lime & Shale	3750	Lime
2070	Lime - hard	3800	Lime
2095	Shale & Lime Shells	3806	Lime
2150	Shale & Shells	3845	Conglomerate
2170	Lime & Shale	3880	Conglomerate
2280	Lime & Shale	3980	Conglomerate
2345	Lime	3992	Arbuckle
2410	Shale & Shells	4007	Total Depth
2485	Shale & Shells		

GEOLOGICAL TOPS

Elevation	2107 RB	Lansing	3490 -1383
Dakota	590 (driller) /1517	Conglomerate	3827 -1720
Anhydrite	1207 (driller) /900	Arbuckle	3991 -1884
Heebner	3442 -1335	Total Depth	4007 -1900

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops, to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

RECEIVED
 MAR 6 - 1957
 3-6-57
 CONSERVATION DIVISION
 WICHITA, KANSAS
 DRILLING
 FILE SEC 6 T 19 R 17W
 BOOK PAGE 144 LINE 45

By

K. T. Woodman
 K. T. WOODMAN