



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of Glickman Oil Company has this

date requested permission to plug the following described well:

Mr. J. M. Glickman guarantees payment of the plugging fee.

Operator's full Name: Glickman Oil Company

Complete Address: Box 3104, Wichita, Kansas

Lease Name: Anshutz Well No. # 1

Location: NE NE SW Sec. 17 Twp. 15 Rge. 12(E) (W)

County Russell Total Depth 3338 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jim Lahar was instructed to plug the well as follows:

8 5/8" 244' Cwc.

Filled hole with heavy mud to 440'; set plug with 1/4 sax
hulls; displaced 25 sax cement thru drill pipe. Mud to 235';
set plug with 1/4 sax hulls; displaced 20 sax cement thru
drill pipe; Mud to 40'; 1/4 sax hulls; plug; displaced 15
sax cement, cementing to base of cellar.

Very truly yours,

Don. Truman
Conservation Division Agent