

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1966
07-13-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Earl Baker of National Coop. Ref. ASSO has this date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: P. O. Box 6, Great Bend, Kansas

Lease Name: Prouse Well No. # 1

Location: C NW NW Sec. 31 Twp. 32 Rge. 6 (E)(W) W

County Harper Total Depth 4873' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Baker was instructed to plug the well as follows:

272' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack of hulls and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent