



CP 2

15-135-70581-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3-17-72
MAR 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Strata Drlg. has this date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg. And Petroleum Resources

Complete Address: Box 18407 Wichita, Ks.

Lease Name: McBee "A" Well No. 1

Location: NW SE NE Sec. 19 Twp. 16 Rge. (E)(W) 26

County: Ness Total Depth 4568' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
70 sk cmt turu drill pipe. Heavy mud to 300' set cementing plug and displace
20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls
and 10 sk cmt to base of cellar.

Very truly yours,

Geo. J. Mearns
Conservation Division Agent