

State of Kansas



15:35-20862-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 19 1974  
4-19-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Cain of Strata Drlg. has this date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg., Inc.

Complete Address: Box 18407 Wichita Kansas

Lease Name: Evel "E" Well No. 1

Location: SW NE Sec. 13 Twp. 16 Rge. (E)(W) 26

County: Ness Total Depth 4555' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Cain was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and ~~displace~~  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo R. Massey  
Conservation Division Agent