

State of Kansas



15-077-19036-00-00

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

*Rec'd  
09-21-1964*

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of Lauck Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman and D. R. Lauck

Complete Address: 1714 First National Bldg., Tulsa, Okla.

Lease Name: Wacker Well No. # 1

Location: C SW NW Sec. 23 Twp. 32 Rge. 5 (E) (W) W

County Harper Total Depth 4760 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Merckle was instructed to plug the well as follows:

223' of 8 5/8" surface pipe, cement circulated with 175 sacks.  
Fill hole with drilling mud to 225', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to the base cellar. Bridge and cement rat hole  
with 2 sacks.

Very truly yours,

*Archie Elving*