



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 20 1964
 01-20-1964
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Leonard Reed of Terrel Drlg. & Producing has this date requested permission to plug the following described well:

Mr. Reed guarantees payment of the plugging fee.

Operator's full Name: Fred B. & Philip F. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Seyb Well No. # 1

Location: C NE SW Sec. 21 Twp. 32 Rge. 5 (E) (W) W

County Harper Total Depth 4767 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reed was instructed to plug the well as follows:

205' of 8 5/8" surface pipe, cemented with 145 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with hulls, cement with 40 sacks. Fill hole with mud to 40', 2nd cementing plug, bridge with hulls, cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent