

2-20

2-100697

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

077

API NUMBER: 15-007-21,235-00-00

C SW NE, SECTION 32 TOWNSHIP 31 RANGE 7W

OPERATOR LICENSE # 5151 3300 FEET FROM S SECTION LINE  
1980 FEET FROM E SECTION LINE

OPERATOR Gear Petroleum Co., Inc.  
NAME & 125 N. Market, #1075  
ADDRESS Wichita, KS 67202

LEASE NAME: Everson #1  
COUNTY: Harper  
WELL TOTAL DEPTH: 3750' 121.87

CONDUCTOR PIPE: \_\_\_\_\_  
SURFACE CASING: 8-5/8" @ 262'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Allen Drilling Company  
ADDRESS: Box 1389, Great Bend, KS 67530 LICENSE: 5418

COMPANY TO PLUG AT: HOUR: 11:30p DAY: 19 MONTH: 2 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Jim Thatcher  
COMPANY NAME: Gear Petroleum PHONE: \_\_\_\_\_

WERE: 35 sx 1470' - 35 sx 950' - 35 sx 310' - 25 sx 60' -  
10 sx RH - 10 sx WW

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (     ) PART (     ) NONE ( X )

COMPLETED: HOUR: 12:30p DAY: 20 MONTH: 2 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Filled hole w/mud to 1470' - spotted 35 sx cmt - pulled  
pipe to 950' - spotted 35 sx cmt - pulled pipe to 310'  
& spotted 35 sx cmt - pulled pipe to 60' & circ 25 sx  
cmt to surf - put 10 sx in rat & 10 sx in water well.

REMARKS: Allied #58845 60/40 4% gel

I DID NOT OBSERVE THIS PLUGGING.

**INVOICED**

RECEIVED

*John L. Sanders*  
J. L. Sanders (AGENT)

DATE 4-5-91

STATE CORPORATION COMMISSION

FORM CP-2/3  
REV. 3/90

INV. NO. 31347 APR 4 1991 04-04-1991

CONSERVATION DIVISION  
Wichita, Kansas

*DW*