

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19028-00-00
Spot: SEÑENE Sec/Twnshp/Rge: 1-18S-11W
4290 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: J MUELLER Well Number: 5
County: BARTON Total Vertical Depth: 3249 feet

Operator License No.: 3309
Op Name: EAGLE PETROLEUM, INC.
Address: PO BOX 106
BUSHTON, KS 67427

Conductor Pipe: Size feet:
Surface Casing: Size 13 feet: 211 **\$105.59**
Production: Size 7 feet: 3245
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/15/2001 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 280 sxs 60/40 pozmix.
Perf at 100' - 580' - 1400'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/15/2001 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

13" S.P. at 211'. 7" casing at 3245' w/250 sxs.
RIH with tubing to 1500' - circulated with 200 sxs cement and 650# hulls.
Pulled all tubing and topped off with 10 sxs cement.
Tied to 7" x 13" annulus - took nothing.
Total of 210 sxs 60/40 pozmix - 10% gel - 650# hulls.

Remarks: ALLIED CEMENTING COMPANY. BRACKEEN LINE CLEANING - WATER.

Plugged through: TBG

District: 04

Signed

Roger D. Moses
(TECHNICIAN)

RECEIVED
11-26-01
NOV 26 2001

KCC WICHITA
NOV 21 2001

INVOICED

DATE 11-27-01
INV. NO. 2002060984

KCC MICHILIB
 17.0-38-38
 (1703838)

1-18-11W
 SE NE NE
 MAGNOLIA PETR. CO #5 J. MUELLER
 Contr. _____ Barton _____ County
 E. 1802 Comm. 9-20-38 Comp. 10-13-38 IP 1605 BOPD

Tops	Depth	Datum
ANHY	560	
LANS	2960	
ARB	3240	
TD	3249	

Casing
 13" 211
 7" 3240

 VSSO 2970-80
 VSSO 2990-3000
 VSSO 3055-60
 PAY 3240-49

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAGNOLIA