

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22372-00-00
Spot: CSWNENE Sec/Twnshp/Rge: 2-18S-12W
4290 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: KINZEL Well Number: 1
County: BARTON Total Vertical Depth: 3464 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, LL
Address: PO BOX 164
ANDOVER, KS 67002

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 222 170 SX CMT
Production: Size 4.5 feet: 3466 150 SX CMT 112.58
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/20/2001 8:00 AM
Plug Co. License No.: 5474 Plug Co. Name: NORTHERN LIGHTS OIL COMPANY, LLC
Proposal Rcvd. from: CURTIS HITCHMAN Company: NORTHERN LIGHTS OIL COMPAN Phone: (316) 733-1515

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 600# hulls.
600' of bad tubing on bottom.
Fluid level 2800'.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 04/20/2001 10:30 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1500' - 775' - 350'.
Tied onto 4 1/2" and pumped 240 sxs with 500# hulls.
Max. P.S.I. 400#. S.I.P. 0#.
Casing annulus pumped 20 sxs with 100# hulls.
Max. P.S.I. 400#. S.I.P. 300#.

INVOICED
DATE 4-27-01
TEL. NO. 2001061724

RECEIVED
STATE CORPORATION COMMISSION
APR 27 2001
4-27-01
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

APR 24 2001

CROSS-TIMBERS OIL CO.
 212 N. MARKET #400
 WICHITA, KS. 67202

REPLACEMENT CARD:
 #1 KINZEL

2-18-12W
 SW NE NE

CONTR MALLARD DRILLING COMPANY CTY BARTON

GEOL WM. SHEPHERD

FIELD WC(3/8 N OF KINZEL;

E 1875 KB CM 5/28/81 CARD ISSUED 9/3/81 IP
 1867 GL

OVER FROM PROD)
 P 45 80 & 25. BWPD
 LKC 3277-3318 OA

+	+
+	+

API 15-009-22,372

LOG	TOPS	DEPTH	DATUM
HEEB		3019	-1144
TOR		3044	-1169
BR LM		3124	-1249
LANS		3138	-1263
ARB		3424	-1549
RTD		3464	-1589

8-5/8" 222/170sx, 4 1/2" 3466/150sx
 DST (1) 3128-3190(LKC)/30-30-60-45,
 GTS 25", GA 15,000 CFG/60", REC
 60' GSY M, 2470' GSY FROGGY O, NW,
 SIP 1079-994#, FP 212-434/530-
 781#
 MICT - CO, PF (LKC) 10/3277-82, 8/
 3300-04, 12/3312-18, AC (3312-18)
 1500 GAL, SWB LD, POP

INFO RELEASED: 9/17/81 - ADDED TOPS &
 DST INFO

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

1-3-1-01