

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20564-00-01
Spot: NWSENW Sec/Twnshp/Rge: 14-19S-15W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: UMMEN OWWO Well Number: 1
County: BARTON Total Vertical Depth: 2021 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

Conductor Pipe: Size _____ feet: 865.68
Surface Casing: Size 8.625 feet: 897 250 SX CMT
Production: Size 4.5 feet: 1997 100 SX CMT
Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/18/2001 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 145 sxs 60/40 pozmix - 10% gel - 200# hulls - 1 sack c.c.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/18/2001 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 4 1/2" and pumped 25 sxs 60/40 pozmix - 10% gel - 4% c.c. with 200# hulls.
Displace with water to 1380'.
Shot casing free at 1328'.
Pulled up to 925' - tied onto and pumped 60 sxs.
Pulled to 350' - tied onto and circulated cement with 65 sxs.
Pulled out of the hole.
Hole standing full of cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

RECEIVED
10-26-01
OCT 26 2001

KCC WICHITA

OCT 23 2001

Signed _____

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE

10-26-01

INV. NO.

2002060861