

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-57739-00-00
Spot: CN2SWNE Sec/Twnshp/Rge: 3-17S-11W
3630 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: BURMEISTER (FREES) Well Number: 3
County: BARTON Total Vertical Depth: 3331 feet

Operator License No.: 6239
Op Name: ZINSZER OIL CO., INC.
Address: PO BOX 211
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 7 feet: 340
Production: Size 4.5 feet: 3324
Liner: Size feet:

8108.26

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/19/2001 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: PERRY S. HENMAN Company: SWIFT SERVICES, INC. Phone: (785) 625-9448

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 1/4# flocele - 200# hulls.
Drilling rig ran into cement plug at 315' - 442' - 540'.
Total TD with rig 730'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/19/2001 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Swift Services ran tubing in hole to 700'.
Tied onto tubing and pumped 50 sxs 60/40 pozmix with cement - circulated to surface.
PTOH. Squeezed with 50 sxs and 200# hulls.
Max. P.S.I. 375#. S.I.P. 250#.
Tied onto backside and pumped in one sack 350# pressure.

INVOICED
DATE 6-26-01
INV. NO. 2001061981

Remarks: SWIFT SERVICES, INC. - TICKET #3503.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

KANSAS CORPORATION COMMISSION CP-2/3

JUN 26 2001

6-26-01

CONSERVATION DIVISION

JUN 29 2001