

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24698-00-00

Spot: S2SWSW Sec/Twnshp/Rge: 20-17S-12W  
~~250~~<sup>350</sup> feet from S Section Line, ~~460~~<sup>460</sup> feet from E Section Line

Lease/Unit Name: SCHILLER

Well Number: 1

County: BARTON

Total Vertical Depth: 3457 feet

Operator License No.: 32639

Op Name: CORAL PRODUCTION CORPORATION

Address: 1600 STOUT STREET, SUITE 1500  
DENVER, CO 80202

Conductor Pipe: Size feet:

Surface Casing: Size 8.625 feet: 537

Production: Size feet:

Liner: Size feet:

*\$ 112.35*

Well Type: DH

UIC Docket No:

Date/Time to Plug: 04/15/2001 7:30 AM

Plug Co. License No.: 9431

Plug Co. Name: VONFELDT DRILLING, INC

Proposal Rcvd. from: DOUG

Company: VONFELDT DRILLING, INC

Phone: (785) 483-6446

Proposed Plugging Method: Order 155 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 04/15/2001 11:30 AM

KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3390' w/25 sxs. Arbuckle 3402'.  
2nd. Plug at 850' w/25 sxs Anhydrite 794' - 830'.  
3rd. Plug at 600' w/80 sxs. Surface pipe set to 537'.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 18 2001  
4-18-01  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 4-19-01  
TEL. NO. 2001061685

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

APR 17 2001