

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23557-00-00  
Spot: CSESENW Sec/Twnshp/Rge: 2-20S-12W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: KNOP - C Well Number: 2  
County: BARTON Total Vertical Depth: 3375 feet

Operator License No.: 3309  
Op Name: EAGLE PETROLEUM, INC.  
Address: PO BOX 106  
BUSHTON, KS 67427

Conductor Pipe: Size feet: 8/109.69  
Surface Casing: Size 8.625 feet: 261 200 SX CMT  
Production: Size 5.5 feet: 3345 100 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/13/2001 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Shot casing off at 1990'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/13/2001 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3290' and topped with 5 sxs using a dump bailer.  
Shot casing off at 1990'.  
Pulled to 1425' and spotted 100 sxs with 300# hulls.  
Pulled to 625' and spotted 40 sxs with 100# hulls.  
Pulled to 250' and circulated cement with 75 sxs.  
POOH. Hole full of cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04


RECEIVED

NOV 15 2001

KCC WICHITA

NOV 14 2001

Signed




(TECHNICIAN)

INVOICED

DATE 11-15-01

INV. NO. 2002060951

PETROLEUM, INC. 2-20-12W  
 800 R. H. GARVEY BLDG. #2 "C" KNOP SE SE NW  
 WICHITA, KS 67202  
 CONTR WOODMAN-IANNITTI CTY BARTON  
 GEOL RALPH WHITE FIELD HAMMER  
 ELV 1800 KB SPD 5/26/84 CARD ISSUED 8/23/84 IP P 25 BOPD  
 ARB OH 3345-3370



LOG	Tops	Depth/Datum
Arh	595	712-5
TOP		2613-813
HEEB		2963-1163
BR LM		3080-1280
LANS		3101-1301
ARB		3338-1538
RTD		3370-1570

API 15-009-23,557  
 8 5/8 " 261 / 200SX, 5 1/2 " 3345 / 100SX  
 DST (1) 3086-3121 (BR LM, LANS) / 15-30-60-120, REC 5' DM,  
 SIP 49-49#, FP 39-39 / 39-39#  
 DST (2) 3116-3136 (LKC) / 15-30-60-120, REC 5' DM, SIP 49-  
 49#, FP 29-29 / 29-29#  
 DST (3) 3172-3205 (LKC) / 15-30-30-30, REC 10' WTRY M, SIP  
 714-645#, FP 29-29 / 29-29#  
 DST (4) 3220-3245 (LKC) / 15-30-30-30, REC 10' M, SIP 94-  
 84#, FP 73-84 / 84-84#  
 DST (5) 3248-3280 (LKC) / 15-30-60-120, REC 70' MDY WTR,  
 SIP 806-785#, FP 42-42 / 42-42#  
 DST (6) 3288-3320 (LKC) / 15-30-60-120, 60' GIP, 35' GSY OILY  
 MUD, 30' OCWM, SIP 157-220#, FP 52-52 / 52-52#  
 DST (7) 3325-3350 (PENN, ARB) / 15-30-60-120, REC 10' SL  
 OCM, SIP 912-933#, FP 21-21 / 21-21#  
 (over)

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS