

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21259-00-00
Spot: NWNENW Sec/Twnshp/Rge: 34-20S-14W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: WOODBURN Well Number: 2
County: BARTON Total Vertical Depth: 3571 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 8 1/6.06
Surface Casing: Size 8.625 feet: 824 325 SX CMT
Production: Size 5.5 feet: 3569 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/04/2002 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2537

Proposed Plugging Method: Order 250 sxs 60/40 pozmix - 10% gel with hulls.
Plug while pulling casing.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/04/2002 3:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

8 5/8" set to 824' w/325 sxs. 5 1/2" set to 3569' w/150 sxs.
Perfs 3422' - 3426'. OH Arbuckle.
Sanded to 3300' and spotted 5 sxs cement with dump bailer.
Shot casing free at 1330'.
Mixed and pumped 95 sxs cement with 300# hulls.
Pulled casing to 875' and pumped 40 sxs cement with 200# hulls.
Pulled casing to 400' and circulated cement with 65 sxs.
Pulled casing with cement in cellar.

RECEIVED
DEC 09 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-10-02

INV. NO. 2003060926

DEC 05 2002

C-G DRLG. CO. 34-20-14W
 1107 DOUGLAS BLDG. #2 WOODBURN APPX NW NE NW
 WICHITA, KS.
 CONTR CO. TOOLS CTY. BARTON
 GEOL. JERRY JESPERSEN FIELD PRITCHARD

E 1911 KPC_M 10/14/77^{CARD} ISSUED 12/15/77 P 67 BOPD + 13 BWPD
 ARB 3569-71

+	+
+	+

API 15-009-21,259

SMP	TOPS	DEPTH	DATUM
ANH	826	+1085	
B ANH	855	+1056	
HEEB	3181	-1270	
BR LM	3285	-1374	
LANS	3294	-1383	
SIMP SD	3535	-1624	
ARB	3564	-1653	
RTD	3571	-1660	

8-5/8" 824/325sx, 5 1/2" 3569/150sx
 NO LOG
 DST (1) 3290-3318/30-30-30-30, 12'M,
 SIP 43-43#, FP 43-43#
 DST (2) 3318-3335/30-30-30-30, 5'M,
 SIP 32-32#, FP 32-32#
 DST (3) 3338-3360/30-30-30-30, 15'M,
 SIP 87-87#, FP 43-43#
 DST (4) 3414-3430/30-30-60-30, 405'
 GIP, 75' HOOM, SIP 109-109#, FP
 43-54#
 DST (5) 3526-3550/30-30-75-30, 125'
 MSW, SIP 87-87#, FP 43-43#
 DST (6) 3542-71/30-30-30-30, 60' GIP
 425' CO, 610' MO, SIP 1082-1082#,
 FP 109-393#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MIC - CO TD, SWB 3 BOPH/5 HRS, POP

MAILED