

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21196-00-00
Spot: SWNENW Sec/Twnshp/Rge: 34-20S-14W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: WOODBURN Well Number: 1
County: BARTON Total Vertical Depth: 3568 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 8 115.96
Surface Casing: Size 8.625 feet: 828 400 SX CMT
Production: Size 5.5 feet: 3567 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/03/2002 12:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREW Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs Arb. OH - 3567'-3568'; LKC 3415'-3419'; 3451'-3455'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/03/2002 2:45 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing sanded bottom to 3360' with sand using a dump bailer followed with 5 sxs cement.
Shot off casing at 2010' - pulled to 1622' and pumped 115 sxs 60/40 pozmix with 300# hulls.
Pulled casing to 875' - pumped 40 sxs 60/40 pozmix with 200# hulls.
Pulled casing to 400' - pumped 60 sxs 60/40 pozmix to circulate cement.
POOH and pulled rest of casing.
Hole standing full of cement.

RECEIVED
DEC 11 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #13171.

Plugged through: CSG

District: 04

Signed 

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-12-02

INV. NO. 2003060931

DEC 09 2002

C-G DRILLING CO.
104 S. BROADWAY
WICHITA, KS.

#1 WOODBURN

34-20-14W
APP SW NE NW

CONTR CO. TOOLS

CTY BARTON

GEOL JERRY JESPERSON

FIELD PRITCHARD EXT

DATE 1909 KB CM 7/5/77 CARD ISSUED 9/8/77 IP P 61 BOPD N/W
LKC 3415-19

+	+
+	+

API 15-009-21,196

LOG	TOPS	DEPTH	DATUM
*ANH		821	+1088
HEEB		3178	-1269
TOR		3197	-1288
DOUG		3210	-1301
BR LM		3282	-1373
LANS		3292	-1383
BKC		3521	-1612
SIMP SD		3532	-1623
*ARB		3564	-1655
LTD		3562	-1653
RTD		3568	-1659
*SMP TOPS			

8-5/8" 821/400sx, 5 1/2" 3567/125sx
DST (1) 3285-3325/30-30-30-30, 60'M
W/SP 0, SIP 583-465# FP 65-65#
DST (2) 3325-3350/30-30-30-30, 80'GIP
10'OCM, 180'HO&GCM, SIP 743-743#
FP 65-108#
DST (3) 3354-3370/30-30-60-30, 60'GIP
180'WM W/F SP 0, 120'W, SIP 860-
196# FP 65-152#
DST (4) 3409-3425/30-30-30-30, GTS/22"
965'FL (345'HO&GCM, 180'GO, 540'
VHO&GCM) SIP 934-913# FP 108-281#
DST (5) 3429-3460/30-30-60-30, 210'
MGSW, 60'SW, SIP 700-626# FP 76-
141#

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

(OVER)

WICHITA

WICHITA