

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19023-00-00
Spot: E2SENV Sec/Twnshp/Rge: 2-17S-11W
3300 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: BURMEISTER Well Number: 1
County: BARTON Total Vertical Depth: 3380 feet

Operator License No.: 31142

Conductor Pipe: Size _____ feet:

Op Name: PETROLEUM PROPERTY SERVICES, INC

Surface Casing: Size 10.75 feet: 276

115 SXS CMT

109.85

Address: 155 N. MARKET, STE 1010
WICHITA, KS 67202

Production: Size 5.5 feet: 3361

175 SXS CMT

Liner: Size 4.5 feet: 3363

Well Type: OIL

UIC Docket No: _____

Date/Time to Plug: 10/04/2001 9:00 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: LARRY WALLERT

Company: PETROLEUM PROPERTY SERVICE

Phone: (316) 265-3351

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Open hole 3363' - 3380'.
Temperature log cement top to surface.
Casing leaks.

Plugging Proposal Received By: PAT STAAB

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/04/2001 11:00 AM

KCC Agent: PAT STAAB

Actual Plugging Report:


Express Well Service RIH with tubing to 2100' - pumped 60 sxs 60/40 pozmix with 350# hulls.
Pulled tubing to 1300' - pumped 80 sxs 60/40 pozmix with 150# hulls. - cement circulated.
Tied onto backside - pumped 40 sxs 60/40 pozmix with Max. P.S.I. 250#. S.I.P. 100#.
Tied onto 10 3/4" casing and pumped 45 sxs with Max. P.S.I. 1000#. S.I.P. 500#.

Remarks: ALLIED CEMENTING COMPANY - TICKET #10331.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

RECEIVED

OCT 10 2001

KCC WICHITA

INVOICED

DATE 10-11-01

INV. NO. 2002060780

Form CP-2/3

OCT 05 2001

CARTER OIL CO

#1

BIRMEISTER

2-17-11W
CE2 SE NW

Contr.

BARTON

County

E 1738

Comm. 12-5-40

Comp. 1-8-40

IP

350 BOPD

Tops	Depth	Datum
TOP	2720	
LANS	3080	
ARB	3350	
TD	3381	

Casing
10" 276
5 1/2" 3361

1 BOPH 3369
A/2000, 2 BOPH, Inc @
3378-80, SWB 3 BOPH/12 hr
set pkr @ 3377; A/1000
SWB 7 BO/1 hr

Ank-747
Sal 1188-1428
Dakota 330

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED

12-11-40
CARTER OIL CO