

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19021-00-00  
Spot: SENE Sec/Twnshp/Rge: 21-17S-14W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: CONNER Well Number: 3  
County: BARTON Total Vertical Depth: 3363 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: PO BOX 2410  
EDMOND, OK 73083

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 837 475 SX CMT  
Production: Size 5.5 feet: 3355 150 SX CMT 109.30  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2001 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2943

Proposed Plugging Method: Ordered out 310 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Prod. Perfs at 2984' - 2987'; 3049' - 3053'; 3064' - 3069'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/16/2001 6:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back to 2950' and topped with 5 sxs cement.  
Shot casing lose at 2000'.  
Parted 20' down.  
Perforated casing at 1560' & 780'.  
Ran tubing to 1550' and pumped 110 sxs cement and 400# hulls.  
Pulled up to 750' and circulated cement with 160 sxs.  
POOH. Hole standing full of cement.

INVOICED  
DATE 5-29-01  
INV. NO. 2001061836

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 22 2001  
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

TRANSWESTERN OIL

#3

CONNER

21-17-14<sup>n</sup>

SE NE NE

Contr. \_\_\_\_\_ BARTON \_\_\_\_\_ County

E 1874 Comm. 1-30-46 Comp. 3-27-46 IP 197 BOPD

Tops	Depth	Datum
ANHY	830	
TOP	3110	
LANS	3210	
CONG	3320	
ARB	3354	
TD	3365	

Casing

8" 837

5" 3355

Pmp 4 BOPH; A/500

SWB 12 BOPH/12 hrs


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

61010-11  
 1-30-46  
 3-27-46