

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-00240-00-00  
Spot: CNWSENE Sec/Twnshp/Rge: 2-16S-13W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: RUDE E Well Number: 1  
County: BARTON Total Vertical Depth: 3360 feet

Operator License No.: 3134 Conductor Pipe: Size \_\_\_\_\_ feet: 8109.20  
Op Name: MORRIS, TERRY E. DBA G L M COMPAN Surface Casing: Size 8.625 feet: 341  
Address: PO BOX 193 Production: Size 5.5 feet: 3360  
RUSSELL, KS 67665 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2001 8:00 AM  
Plug Co. License No.: 3134 Plug Co. Name: MORRIS, TERRY E. DBA G L M COMPANY  
Proposal Rcvd. from: TED LEUBBERS Company: MORRIS, TERRY E. DBA G L M CO Phone: (785) 483-2123

Proposed Plugging Method: Ordered out 310 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/18/2001 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 450' - 870' - 1575'.  
Tied onto casing and pumped to pressure with 285 sxs cement and 500# hulls.  
Max. P.S.I. 500#. S.I.P. 300#.  
Hooked onto annulus and pumped 15 sxs cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
DEC 26 2001  
WICHITA

INVOICED

Form CP-2/3

DATE 12-28-01

INV. NO. 2002061098

DEC 19 2001

RECEIVED  
 JUN 10 1959  
 ATTIQUIN/200

K & E DRILLING, ET AL #1 RUDE WEL 2-16-59  
 NW SE NE

Contr. K & E DRILLING BARTON County

E1902RB Comm. Comp. 2-27-59 166 BORD  
 PHY POT

Tops	Depth	Datum	Casing
ANH	850	1052	8" 341 5" 3360
HEEB	3002	1100	DST: 3096-3130/13 HR: G/L HR: 460' O & GCM: 260' O & GCM: 60' H OCM: 420' O & MDY O: BHP: 870
BR LM	3084	1182	DST: 3132-70/1 HR: G/45" 70' HO & GCM: 980' O & MDY O: 90' W: BHP: 865
LANS	3093	1191	DST: 3170-95/1 HR: 10' W: BHP: 980
			CO: 3354 PERF: 16/3348-52: ACID: 500: 5 1/2 BWP PLUG: 16/3169-73: ACID: 1500: 12/31/4-17
ARB	3344	1442	8/31/39-11: 10 BOPH, NATL: 12/31/22-25: 13 BOPH, NATL: 16/3100-04: 5 BOPH, NATL: ACID NEY SW POOL OPENER: 1000: 5 1/2 BOPH: 29 BO (ALL ZONES)
TD	3360	1458	NAMED BY: NOMENCLATURE COMM 2-3-59

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS