

TO: **STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202**

API Well Number: 15-009-04228-00-00
Spot: CSESWNW Sec/Twnshp/Rge: 22-18S-11W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: OBERLE B Well Number: 2
County: BARTON Total Vertical Depth: 3344 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY
Address: 7130 S. LEWIS, STE 910
TULSA, OK 74136

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 598 325 SX CMT
Production: Size 5.5 feet: 3328 150 SX CMT *108.68*
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/07/2001 4:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Order 150 sxs 60/40 pozmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 05/07/2001 7:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

8 5/8" set to 598' w/325 sxs. 5 1/2" set to 3328' w/150 sxs.
Sanded to 3290' and spotted 5 sxs cement with dump bailer.
Shot casing below salt section but not free.
Shot casing loose at 830'.
Mixed and pumped 60 sxs cement with 300# hulls.
Pulled casing to 200' and circulated cement with 70 sxs.
Pulled casing and topped with 15 sxs.

INVOICED
DATE 5-10-01
INV. NO. 2001061790


RECEIVED
KANSAS CORPORATION COMMISSION
MAY 10 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)