

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07390-00-00
Spot: CNESENE Sec/Twnshp/Rge: 28-20S-12W
3630 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: SPACIL Well Number: 4
County: BARTON Total Vertical Depth: 3437 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 253 225 SX CMT
Production: Size 4.5 feet: 3424 150 SX CMT \$ 111.70
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/11/2001 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2943

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perfs 1325' and 625'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/11/2001 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

May 10, 2001 - Log Tech ran into hole and shot perfs at 1325' and 625'.
May 11, 2001 - Mike's Testing ran tubing in hole to 1500'. Tied onto tubing and pumped 125 sxs cement with 600# hulls to circulate to surface.
Pulled tubing and tied onto casing with swedge - pumped 15 sxs and blew hole in top of casing.
Welded hole shut. Tied back onto casing and pumped an additional 35 sxs into casing for a total of 175 sxs.
Pumped in pressure 300#. Max. P.S.I. 500#. S.I.P. 400#.
Tied onto backside - pumped 10 sxs with pump in Max. P.S.I. 500#. S.I.P. 400#.

INVOICED
DATE 5-29-01
INV. NO. 2001061837

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 22 2001

CONSERVATION DIVISION

BBB

Remarks: ALLIED CEMENTING COMPANY - TICKET #8237

Plugged through: TBG

District: 04

Signed

Pat Staab

(TECHNICIAN)

ALPINE OIL & ROYALTY

#4 SPACIL

28-20-12W
NE SE. NE 53

Contr. QUAKER DRILLING

BARTON County

E 1837RB Comm.

Comp. 2-24-56 IP 202 BOPD/ARB

Tops	Depth	Datum
HEEB	3024	-1187
BR LM	3148	-1311
LANS	3166	-1329
CONG	3400	-1563
ARB	3420	-1583
TD	3437	-1600

Casing
4" 3424

DST 3389-3437/1 HR, 50' GCM
120' 0 & GCM, BHP 850#
CO 3437: 2700' OIH/12 HR:
ACID 500: SWB 32.80/3 HR

WORKMAN POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS