

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07475-00-00
Spot: CNWNESW Sec/Twnshp/Rge: 28-19S-12W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: JOHNSON AB Well Number: 3
County: BARTON Total Vertical Depth: 3399 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 250
Production: Size 5.5 feet: 3384 w/190 sxs cmt \$110.47
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2001 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2943

Proposed Plugging Method: Ordered out 220 sxs 60/40 pozmix - 10% gel - 400# hulls.
Emergency plug with rig over the hole.
Casing part at 400'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/14/2001 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Rigged up to back off casing and replace when casing fell over.
RIH with tubing to 600' and stacked out.
Decided to P&A.
Tied onto tubing and pumped 150 sxs with 200# hulls.
POOH.
Rigged up on 5 1/2" and pulled to 200'.
Tied onto and circulated with 65 sxs.
POOH. Hole standing full of cement.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 18 2001

CONSERVATION DIVISION

INVOICED

DATE 6-18-01

INV. NO. 2001061962

Remarks: LEASE ALSO KNOWN AS JOHNSON #3. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

GRAHAM-MESSMAN-RINEHART

#3

JOHNSON

28-19-12W / 53
NW NE SW

Contr. _____ BARTON _____ County

E 181.6RB Comm. _____ Comp. 11-9-51 IP 85 BOPD (LANS)
PHY PG


Tops	Depth	Datum
ANH	632	1184
LANS	3130	-1314
CONG	3377	-1561
ARB	3383	-1567
T.D.	3395	-1579

Casing

8" 250
5" 3384

OP:DD 3389:ACID 1000
 DST 3131-3205, 40 MIN, 20' OCM
 DST 3268-92, 30 MIN, 125' OCM
 1251 CLEAN OIL:BHP 850#
 DST 3299-3315, 30 MIN, 32' O &
 GCM:BHP 350#
 DD 3389:ACID 1000:SWB 18 GPH
 ACID 500:SWB 2 BOPH/4 HRS
 PERF 24s 3322-30:ACID 1000:
 SWB 3/4 BOPH/3 HRS:PB 3312:
 PERF 23s 3298-3306:ACID 1000
 SWB & FLOW 20 BOPH/3 HRS:POP

FT ZARAH POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS