

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23461-00-00  
Spot: NENW Sec/Twnshp/Rge: 18-16S-11W  
4620 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: KRIER Well Number: 1-A  
County: BARTON Total Vertical Depth: 3312 feet

Operator License No.: 6357  
Op Name: WEBCO OIL CO., INC.  
Address: 1303 BAKER AVE.  
GREAT BEND, KS 67530

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 274 175 SX CMT  
Production: Size 5.5 feet: 3304 175 SX CMT  
Liner: Size feet: \$107.64

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/12/2001 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Shot casing loose at 1800'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/12/2001 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3250' and topped with 5 sxs cement using a dump bailer.  
Shot casing loose at 1800'.  
Pulled up to 1400' - tied onto and pumped 100 sxs with 400# hulls.  
Pulled to 680' - spotted 30 sxs with 100# hulls.  
Pulled to 300' and circulated cement with 85 sxs.  
POOH. Hole standing full of cement.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 17 2001

CONSERVATION DIVISION

INVOICED

DATE 7-17-01

INV. NO. 2002060077

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed


Jay Pfeifer

(TECHNICIAN)

JUL 13 2001

L. D. DAVIS / L. D. DRILLING  
 RT. #1 BOX 1852B #1 "A" KRIER 18-16-11W  
 GREAT BEND, KS 67530 C NE NW  
 CONTR COMPANY TOOLS CTY BARTON

GEOL FIELD KRAFT-FRUSA



ELV 1873 KR SPD 2/27/84 CARD ISSUED 4/5/84 P 20 BO & 13 BWPD  
 1867 GL ARB OH 3304.5-3307

LOG	Tops	Depth/Datum	API 15-009-23,461
*ANH		729-1144	8 5/8 " 274/175SX; 5 1/2 " 3304.5/175SX
*B/ANH		751-1122	DST (1) 2847-60 (SHAW) / 30-30-60-45, 700' GIP, REC 55'
HEEB		2911-1038	HOCM (25% OIL) SIP 236-411#, FP 27-30 / 30-34#
TOR		2930-1057	DST (2) 3043-56 (LKC) / 30-30-60-45 GTS/50" TSTM, REC 40'
DOUG		2942-1069	GSY M, W/FEW OIL SPKS, SIP 381-355#, FP 55-55 / 56-58#
BR/LM		3005-1132	DST (3) 3101-18 (LKC) / 30-30-30-30, REC 50' OIL SPKD THIN
LANS		3023-1150	MUD, SIP 613-582#, FP 36-40 / 40-43#
BKC		3260-1387	DST (4) 3270-3307 (PENN, ARB) / 30-45-60-45, 300' GIP, REC
ARB		3305-1432	1060' GSY-FROTHY OIL, SIP 1027-1018#, FP 127-281 / 260-
RTD		3307-1434	453#
*SAMPLE TOPS			MICT - CO, (ARB OH), SWB DWN, GSO, NAT, POP, P 20 BO & 13 BWPD

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS