

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24694-00-00  
Spot: E2NE Sec/Twnshp/Rge: 24-17S-13W  
1320 feet from N Section Line, 580 feet from E Section Line  
Lease/Unit Name: CORRINE FINGER Well Number: 1  
County: BARTON Total Vertical Depth: 3363 feet

Operator License No.: 32639  
Op Name: CORAL PRODUCTION CORPORATION  
Address: 1600 STOUT STREET, SUITE 1500  
DENVER, CO 80202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 520 275 SX CMT  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 12/14/2000 10:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: SALLY BYERS Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: Ordered out 155 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack.

109.30

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 12/14/2000 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

1st. Plug at 3328' w/15 sxs.  
2nd. Plug at 770' w/25 sxs.  
3rd. Plug at 570' w/80 sxs.  
4th. Plug at 40' w/10 sxs.  
15 sxs in rathole.  
10 sxs in mousehole.


INVOICED  
DATE 4-10-01  
INV. NO. 2001061605

Remarks: SPOT LOCATION SHOULD READ 80' E.OF E2NE 24-17-13W.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CORAL PRODUCTION CORP  
DENVER CO 80202

WILUCA1

24-17S-13W  
80'E, C E/2 NE

#1 FINGER, CORBINE

site 2-1/4 N & 3-1/4 E OF HOISINGTON KS  
contr: DUKE DRILLING #8  
geol: TIM LAUER

dr: BARTON AP# 15-009-24694  
field WC (1 E OF HOISINGTON  
EAST)


fr date 11/28/2000 spd date 12/05/2000 drig comp 12/13/2000 card issued 02/12/2001 last revised 02/12/2001

ELV: 1859 KB, 1851 GL LOG  
tops.....depth/datum  
ANH.....750 +1109  
B/ANH.....778 +1081  
TOP.....2724 -865  
HEEB.....3008 -1149  
BR LM.....3097 -1238  
LANS.....3111 -1252  
BKC.....3346 -1487  
ARB.....3355 -1496  
RTD.....3357 -1498  
LTD.....3363 -1504

IP status  
D&A, ARB, 12/13/2000  
CSG: 8-5/8" 519.75 / 275 SX (ALT 1)  
COMMENT: MI & RURT 12/4/2000  
NO CORES  
DSTS TAKEN - DETAILS NA  
TRGT ZN: ARB, LKC (OIL), PTD 3400 (ARB), D & A  
12/13/2000 - NO OTHER INFO AVAILABLE - TEMP COMP  
2/12/2001

COPYRIGHT 2001  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS