

TO: . . .  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24277-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 9-18S-14W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: WHITEMAN Well Number: 1  
County: BARTON Total Vertical Depth: 3650 feet

Operator License No.: 3536  
Op Name: RAMCO ENERGY CORPORATION  
Address: 2699 STIRLING ROAD, SUITE C102  
FT. LAUDERDALE, FL 33312

Production Casing Size: 5.5 feet: 3635 160 SX CMT  
Surface Casing Size: 8.625 feet: 344 165 SX CMT

*\$ 118<sup>63</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2003 5:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 210 sxs 60/40 pozmix - 10% gel - 700# hulls.  
Perfs at 3434' - 3442'. PBD at 3611'.  
Dakota 90' - 365'. Anhy. 889' - 914'. Salt 1339' - 1624'.

Plugging Proposal Received By: PAT STAAB Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/09/2003 6:30 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Sanded bottom of hole to 3280' with 5 sxs cement on top with dump bailer.  
Shot perfs at 1650' - 910' - 375'.  
RIH with tubing to 1650' and pumped 150 sxs 60/40 pozmix with 700# hulls mixed in to circulate cement to surface.  
Pulled tubing - tied onto casing with a swedge and pumped up backside.  
Pumped 10 sxs to circulate cement out backside.  
Shut in backside and pumped an additional 50 sxs 60/40 pozmix.  
Max. P.S.I. 500#. S.I.P. 450#.

RECEIVED  
JUN 24 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #14730.

Plugged through: TBG

District: 04

Signed *Pat Staal*  
(TECHNICIAN)

*AD*

INVOICED

DATE 6-24-03

TIME 20030616.91

JUN 17 2003

replacement card

PENDLETON LAND & EXPLORATION & RAMCO DRILLING  
PLAINVILLE, KS 67663

9-18 -14W  
SW SW NE

#1 WHITEMAN

site: 1/2 S & 4-1/2 W OF HOISINGTON, KS  
contr: ALLEN DRILLING COMPANY  
geol: ROBERT SMITH

city: BARTON  
field: BOYD

API 15-009-24277

fr date	spd date	drig comp	card issued	last revised
11/18/87	11/20/87	11/26/87	03/16/88	05/17/89


ELV: 1945 KB SMP  
 tops.....depth/datum  
 HEEB.....3109 -1164  
 BR LM.....3179 -1234  
 LANS.....3189 -1244  
 ARB.....3418 -1473  
 PBDT.....3611 -1666  
 RTD.....3650 -1705

IP status:  
 OIL, P 7 BO & 243 BWPD, ARB 3434-3447 OA,  
 INFO RELEASED: 5/17/89 - ADDED TOPS & DSTS  
 NOTE: INFO RELEASED: 9/28/88 - WAS OIL WELL -  
 TIGHT HOLE  
 CSG: 8-5/8" 344 / 165 SX, 5-1/2" 3635 / 160 SX  
 NO CORES  
 DST (1) 3183-3265 (LKC), / 30-60-60-90, 180' GIP, REC  
 30' OIL & GCM: ISIP 634# FSIP 634# IFP 72# -72#  
 FFP 72# -72# IHP 1651# FHP 1620# BHT 104 °  
 DST (2) 3320-3380 (LKC), / 30-30-30-30, REC 5' M; W /  
 SPTS OIL ISIP 41# FSIP 41# IFP 41# -41# FFP 41#  
 -41# BHT 105 °

PENDLETON LAND & EXPLORATION & RAMCO DRILLING  
PLAINVILLE, KS 67663

9-18 -14W  
SW SW NE

#1 WHITEMAN

DST (3) 3382-3433 (ARB), / 30-60-60-90, 180' GIP, REC 65' CLEAN OIL, 115' MDY GSY OIL  
 ISIP 997# FSIP 1049# IFP 52# -52# FFP 72# -93# IHP 1703# FHP 1692# BHT 108 °  
 DST (4) 3433-3448 (ARB), / 30-60-30-60, 330' GIP, REC 205' CLEAN OIL, 125' MDY GSY OIL, 60'  
 OIL & GCMW, 120' SLI OCW ISIP 1112# FSIP 1112# IFP 52# -104# FFP 145# -187# IHP  
 1724# FHP 1703# BHT 112 °  
 MICT - CO, PF (ARB) 3434-3442, W / 4 SPF, AC 250 GAL (15% MCA W / HAMPENE), SO, POP,  
 OIL WELL (POTENTIAL NOT RPTD) 2/14/88, OFF PMP 7/25/88, PF (ARB) 3443-3447, W / 4 SPF,  
 AC 250 GAL XYLENE & 750 GAL (15% SWIC), SO, SET 2-7/8" TBG AT 3500, POP, P 7 BO & 243  
 BWPD