

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04128-00-00
Spot: CNWNENE Sec/Twnshp/Rge: 20-17S-14W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: DIRREEN Well Number: 1
County: BARTON Total Vertical Depth: 3406 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 2410
EDMOND, OK 73083

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 875 500 SX CMT
Production: Size 5.5 feet: 3398 125 SX CMT \$ 110.70
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2001 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2943

Proposed Plugging Method: Ordered out 310 sxs 60/40 pozmix - 10% gel - 200# hulls.
Prod. Perfs at 3014' - 3022'; 3088' - 3092'; 3149' - 3151'.
Shot off casing at 2410'.

Plugging Proposal Received By: BRUCE BASYE

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/15/2001 11:00 AM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back to 2960' and topped with 5 sxs using a dump bailer.
Shot casing off at 2410'.
Pulled to 1560' and pumped 130 sxs - 200# hulls.
Pulled to 860' and circulated cement with 110 sxs.
POOH.
Hole standing full of cement.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 22 2001
INVOICED
DATE 5-29-01
INV NO. 2001061836 CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

BOB

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

SUNRAY OIL CORPORATION

#1

DIRREEN

20-17-14W

52

NW NE NE

Contr.

BARTON

County

E 1904 Comm.

Comp. 11-3-50

IP 268 BOPD

Tops	Depth	Datum
HEEB	3071	-1167
BR LM	3137	-1233
LANS	3146	-1242
CONG	3365	-1461
ARB	3395	-1491
T.O.	3406	-1502

Casing

8" 875

5" 3398

CORRECTED CARD

11-10-50

500' 01H/1 HR

CORRECTED CONG.

BOYLE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

5700800
 DTAC
 500' 01H/1 HR