

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22753-00-00

Spot: CSWSENE

Sec/Twnshp/Rge: 26-19S-11W

2870 feet from S Section Line, 940 feet from E Section Line

Lease/Unit Name: ISERN

Well Number: 1

County: BARTON

Total Vertical Depth: 3312 feet

Operator License No.: 4707

Op Name: BOXBERGER, CARL OIL, INC.

Address: PO BOX 1604 3111 - 10TH STREET STE 1
GREAT BEND, KS 67530

Conductor Pipe: Size

feet:

Surface Casing: Size 8.625

feet: 212

w/165 sxs cmt

Production: Size 4.5

feet: 3303

Liner: Size

feet:

8107.64

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/12/2001 10:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed
Plugging
Method:

Ordered out 230 sxs 60/40 pozmix - 10% gel - 500# hulls.
Shoot casing free at 3322'.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/12/2001 12:15 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:


Sanded back casing to 3250' and topped with 5 sxs cement using a dump bailer.
Shot casing free at 3322'.
Pulled up to 1300' and spotted 90 sxs with 300# hulls.
Pulled to 500' and spotted 30 sxs with 200# hulls.
Pulled to 200' and circulated cement wit 65 sxs.
POOH. Hole full of cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED

SEP 18 2001

KCC WICHITA

INVOICED

DATE

9-18-01

INV. NO.

2002060487

Form CP-2/3

SEP 13 2001

PV PROPERTIES, INC.
400 N. WOODLAWN, #101
WICHITA, KS 67208
CONTR LOBO DRLG. CO.

26-19-11W
#1 ISERN APPROX. SW SE NE

CTY BARTON

GEOL

FIELD CHASE-SILICA

E 1772 KB CM 4/3/82 CARD ISSUED 9/16/82 IP OIL WELL
ARB OH 3303-3312

API 15-009-22,753

+	+	+
+	+	+
+	+	+

Sample Log Tops Depth/Datum

NO TOPS AVAILABLE

RTD 3312-1540

Independent Oil & Gas Service
Wichita, Kansas

8 5:8 - 212:165SX; 4 1:2 - 3303
MCT - CO. (ARB OH), TSTO. POP. OIL WELL - NO OTHER INFO TO
BE RELEASED AT PRESENT - WILL RELEASE INFO WHEN AVAIL-
ABLE. TEMP COMP 9/16/82

MAJOR

MAJOR

MAJOR