

To: 1 071068
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
202 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-12

API NUMBER 15- 135-22,831-0000 2112
SW SW NW, SEC. 19, T. 16 S, R. 26 W/E
2970 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9476
Operator: G-D Oil Operations
Name & Address 207 S. Broadway
Wichita, KS 67202

Lease Name Horchem Well # 1
County Ness 148.03
Well Total Depth 4555 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor G-D Oil Operations License Number 9476
Address 207 S. Broadway, Wichita, KS 67202

Company to plug at: Hour: 4 p.m. Day: 12 Month: 5 Year: 1992

Plugging proposal received from Glenn Drotts
(company name) G-D Oil Operations (phone) 316-267-2858

Work: 4 1/2" at 4548' w/175 sx cement, Perfs 4037-4480', Open hole 4548-55' 2-staged-DV @ 2106';
cement to 0' w/500 s;
1st plug pump 800 lbs. hulls and 230 sx cement down 4 1/2".

Check backside.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 12 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 800 lbs. hulls and 230 sx cement down 4 1/2".

Maximum pressure 1200 psi and shut in 0 psi.

2nd plug backside took 20 sx cement to 600#.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If applicable, observe this plugging.)

DATE 6-5-92

INV. NO. 35417

5-12 JUL 08 1992

Signed Dan Goodrow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
MAY 15 1992
5-15-92