

To: 1 071054  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-17 API NUMBER 15- 135-23,592-0000 120R

TECHNICIAN'S PLUGGING REPORT

Operator License # 6622  
Operator: Jason Oil Company  
Name & Address: P.O. Box 701  
Russell, KS 67665

NW NW NE, SEC. 26, T. 16 S, R. 26 W/E  
4950 feet from S section line  
2310 feet from E section line

Lease Name U.G.M.C. Well # 1  
County Ness 149.50  
Well Total Depth 4600 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 17 Month: 4 Year: 19 92

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4599', Perfs at 4536-38'  
1st plug sand back to 4480' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 50 sx cement at 1900', 3rd plug pump 80 sx cement at 1200',  
4th plug pump 30 sx cement at 600', 5th plug pump 40 sx cement at 290',  
6th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:30 a.m. Day: 17 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 4 sx cement on top of sand through bailer,  
2nd plug pumped down 4 1/2" with 80 sx cement at 1200',  
3rd plug pumped 30 sx cement at 600',  
4th plug pumped 40 sx cement at 290',  
5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1700' of 4 1/2" casing  
(if additional description is necessary, use BACK of this form.)

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 24 1992  
4-24-92  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 4-28-92  
INV. NO. 35-073

Signed Dan Jordan  
(TECHNICIAN)



# WIRE-TECH

# RADIATION GUARD LOG

COMPANY JASON OIL, CO. /5-135-23592-0000  
 WELL #1 U. G. M. C.  
 FIELD \_\_\_\_\_  
 COUNTY NESS STATE KANSAS  
 Location \_\_\_\_\_  
                   NW NW NE  
 Sec. 26 Twp. 16S Rge. 26W

Other Services:  
 \_\_\_\_\_  
 \_\_\_\_\_

Permanent Datum GROUND LEVEL Elev. 2612'  
 Log Measured From KELLY BUSHING 5 Ft. Above Perm. Datum  
 Drilling Measured From KELLY BUSHING

Elev. KB. 2617'  
 D.F. \_\_\_\_\_  
 G.L. 2612'

Date	9-3-91	<b>RECEIVED</b> KANSAS CORPORATION COMMISSION  <b>JAN 15 1992</b>  CONSERVATION DIVISION WICHITA, KS
Run No.	ONE	
Depth—Driller	4600'	
Depth—Wire Tech	4600'	
Bl. Log Inter.	4599'	
Top Log Inter.	0	
Casing—Driller	8 5/8" @ 261'	
Casing—Wire Tech		
Bit Size	7 7/8"	
Type Fluid in Hole	CHEMICAL MUD	
Dens.   Visc.	9.5   48	
pH   Fluid Loss	9.5   10.0	
Source of Sample	FLOWLINE	
R <sub>n</sub> @ Meas. Temp.	1.3 @ 77 °F	.35 @ 120°F
R <sub>nl</sub> @ Meas. Temp.	.93 @ 77 °F	.61 @ 120°F
R <sub>mc</sub> @ Meas. Temp.	1.82 @ 77 °F	1.20 @ 120°F
Source R <sub>nl</sub> /R <sub>mc</sub>	CHARTS I	
R <sub>m</sub> @ BHT	.85 @ 120 °F	
Time Since Circ.	3.5 HOURS	
Max. Rec. Temp.	120°F @ T.D.	
Equip.   Location	60 GREAT BEND, KANSAS	
Recorded By	W. CURTIS	
Witnessed By	L. CHUBB	