

1 070714

8-11

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,066-0000
C NE NE, SEC. 25, T 16 S, R 26 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Stutz Well # 1

Operator Name & Address Thunderbird Drilling, Inc.

County Ness 147.19

Address P.O. Box 97

Well Total Depth 4529 feet

Ellinwood, KS 67526

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 356

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131

Address P.O. Box 97, Ellinwood, KS 67526

Company to plug at: Hour: 10:15 a.m. Day: 11 Month: 8 Year: 19 89

Plugging proposal received from Maynard Weber

(company name) Thunderbird Drilling, Inc. (phone) 316-564-2577

were: 4 1/2" at 4522' Open hole 4522-29'

1st plug sand back to 4470' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 70 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 11 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug bailed 4 sx cement at top of fish at 3755',

2nd plug pumped 400 lbs. hulls, 70 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement down 8 5/8". Maximum pressure 500 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1989

8-15-89

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1397' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If necessary) observe this plugging.

Signed Dan Johnson
(TECHNICIAN)

DATE 8-18-89

INV. NO. 25680