

1050164

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE NE NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,526-0000

_____ , SEC. 29 , T 16 S , R 26 W/E
990 feet from N/SX section line
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5104

Lease Name Shellenberger Well # 2

Operator: Blue Goose Drilling Co.
Name & Address P. O. Box 1413
Great Bend, KS 67530

County Ness
Well Total Depth 4622 150.21 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 387

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Company Tools License Number 5104

Address P. O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 12 Noon Day: 2 Month: March Year: 19 84

Plugging proposal received from Leroy Boren

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2100' with 50 sx cement

2nd plug at 1020' with 50 sx cement

3rd plug at 450' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement
Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 3:30 pm Day: 2 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1020' with
50 sx cement, 3rd plug at 450' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole
with 15 sx cement.

Bob Tarbutton gave the orders, Richard Lacey saw part of the job.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

DATE 3-9-84

MAR 07 1984
3-7-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)