

1 060056

1-25

175 R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,544-0000  
NW SW SW, SEC. 24, T 16 S, R 26 W&K  
990 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7200

Lease Name Jones Well # 4

Operator: Scott T. Lutz

County Ness 150.41

Name & Address P.O. Drawer D

Well Total Depth 4628 feet

Shell Knob, MO 65747

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 506, Russell, KS 67665

Company to plug at: Hour: 3 a.m. Day: 25 Month: 1 Year: 19 91

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2007-41'  
1st plug at 2050' with 50 sx cement, 2nd plug at 1150' with 50 sx cement,  
3rd plug at 675' with 40 sx cement, 4th plug at 300' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:15 a.m. Day: 25 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2050' with 50 sx cement,

2nd plug at 1150' with 50 sx cement, 3rd plug at 675' with 40 sx cement,

4th plug at 300' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(if additional description is necessary, use BACK of this form.)

**INVOICED**

FEB 12 1991

DATE

INV. NO. 30696

Signed Case Morris  
(TECHNICIAN)

EFFECTIVE DATE: 12-15-90

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas

NOTICE OF INTENTION TO DRILL.

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

135-23,544-0000

Alt 2

Expected Spud Date January 1 1991  
month day year

NW SW SW4 Sec 24 Twp 16 S, Rg 26W East West

OPERATOR: License # 7200  
Name: Scott T. Lutz  
Address: P. O. Drawer D  
City/State/Zip: Shell Knob, Mo. 65747  
Contact Person: H.L. Maddox  
Phone: 316-653-4178

990 feet from South line of Section  
4950 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: UNKNOWN  
Name: Emp 4985

County: Ness  
Lease Name: Jones Well #: 4  
Field Name: Arnold  
Is this a Prorated Field? yes X no  
Target Formation(s): Mississippi  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: NA feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 150'  
Depth to bottom of usable water: 1175'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 350'  
Length of Conductor pipe required: None  
Projected Total Depth: 4650'  
Formation at Total Depth: 4600'  
Water Source for Drilling Operations:

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj X Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWMO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OWMO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_

STATE OF KANSAS COMMISSION

JAN 31 1991

Pusher Tom Alm SPUD DATE 1-17-91 INIT. CM

LENGTH SURFACE PLANNED 250

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 7/8 @ 266' CONDUCTOR  
ANHYDRITE T- 2007 B- 2041 ELEVATION

TD 4628 FORMATION Miss.

RAN PIPE @	DV TOOL	ALT II DONE
SX	SX	Y N
Arbuckle Plug @	Ft. W/	SX
Hug./Council @	Ft. W/	SX
Anhydrite Base @	2050 Ft. W/	50 SX
1/2 Base Anyh. @	1150 Ft. W/	50 SX
1/2, 1/2 Plug @	675 Ft. W/	40 SX
Bottom Surface @	300 Ft. W/	40 SX
40' Plug @	40 Ft. W/	10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well) Pond \_\_\_\_\_  
TECHNICIAN CM DATE 1-24-91 Hauling \_\_\_\_\_

TYPE OF CEMENT 60/40 670 1/4" flow seal

STARTING TIME 3:00 (AM/PM) DATE 1-25-91

COMPLETION TIME 6:15 (AM/PM) DATE 1-25-91

CEMENT COMPANY Habitacion