

CP3



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-SE-SW

SEC. 17 TWP. 15 RGE. 12 W

Dry Hole ~~_____~~ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Anschutz

Operator Fred Anschutz Address Box 650, Hays, Kas.

Field _____ County Russell

Total Depth 3327 Feet.

RECEIVED
STATE CORPORATION
COMMISSION
KANSAS
JAN 8 - 1949
RCMD
01-08-49

(Describe briefly the manner in which the well was plugged)

8 1/2 @ 230. Circulated with cement. 5 1/2 @ 3315 -
have wells plugs to 3078. Part @ 3040 - Heavy
mud 3040 to 3025 - 5 sac cement. 5 1/2 ripped
& pulled. Heavy mud to 230 - Hard plug - ran
15 sac cement - Heavy mud to 30 -
Hard plug - ran 10 sac cement -

Leon Peety
District Conservation Agent

Date 1-4-49

PLUGGING
FILE SEC 17 T 15 R 12W
BOOK PAGE 79 LINE 1

Handwritten mark resembling a stylized '7' or 'F' with a horizontal line extending to the right.