

15-077-30108-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1966
07-13-1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address: P. O. Box 6, Great Bend, Kansas

Lease Name Prouse Well No. # 1

Location C NW NW Sec. 31 Twp. 32 Rge. 6 (S) (W) W

County Harper Total Depth 4873'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1:00AM Day 11th Month July Year 1966

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cement circulated. Hole was filled with
drilling mud to 260', 1st cementing plug, bridged with 2 sacks of dry
cement and 1/2 sack of hulls on fluid at 260', and cemented with 23 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and
cemented with 9 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/13/66
INV. NO. 3561-W