

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -017-20532-00-00 (of this well)

Operator's Full Name Sanders Oil Co.

Complete Address 910 Sutton Pl., Wichita, Ks. 67202

Lease Name Parson Well No. 1

Location NW SE NW Sec. 29 Twp. 32s Rge. 6 (E) (W) X

County Harper Total Depth 4890

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 2:45 Pm. Day 8 Month 9 Year 1980

The above well was plugged as follows:

237' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 4648' w/125
sax cement. Preforated at 4450-56'-Allied mixed & pumped 35 sax common
cement to 4320'-Pull 3866' casing-Allied mixed & pumped 8 sax hulls
25 sax gel-100 sax 50/50 posmix cement w/4% gel & 3% cc to top of
casing. Shut in w/700# pressure.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1980

CONSERVATION DIVISION
Wichita/Kansas

I hereby certify that the above well was plugged as herein stated

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE

9-12-80

INV. NO.

3091W