

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 077-20546-00-00 (of this well)

Operator's Full Name Sanders Oil Co.

Complete Address 910 Sutton Pl., Wichita, Ks. 67202

Lease Name Coulson Well No. 1

Location SW SE Sec. 24 Twp 32s Rge. 7 (E) (W) W

County Harper Total Depth 4925

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 4:45 Pm Day 8 Month 9 Year 1980

The above well was plugged as follows:

246' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 4555' w/110
sax cement. Preforated at 4485' to 92'-Allied mixed & pumped in 4 1/2"
casing 35 sax common cement to 4320'-Pull 3688' casing. Allied mixed
& pumped in 8 5/8" casing 8 sax hulls-25 sax gel-100 sax 50/50 posmix
cement w/4% gel & 3% cc to top of casing. Shut in w/500# pressure.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1980

09-11-1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 9-12-80
INV. NO. 3090w