

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
245 North Market  
Wichita, Kansas 67202

MAR 26 1976  
03-26-1976  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 077 - 20344 - 00 - 00 (of this well)

Operator's Full Name McCoy Petroleum Co

Complete Address 502 Union Center Wichita, KS

Lease Name Burkholder Well No. 1

Location C SW/SW Sec. 21 Twp. 32 Rge. 7 (E) (W) W

County Harper Total Depth 4416

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Oilfield Service

Address 107 W Fowler Medicine Lodge, KS License No. 583

Operation Completed: Hour 1:00 PM Day 25 Month 3 Year 1976

The above well was plugged as follows:  
263 ft 8 5/8 surface cemented with 150 sacks. 4407 ft 4 1/2 long string  
cemented with 115 sacks. Top perf. 4388 ft. Sand to 4375 ft, 4 sacks  
cement with bailer. Pulled 3750 ft 4 1/2. Set 10 ft rock bridge at  
240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell B. Schuster  
Well Plugging Supervisor

DATE 3-29-76

INV. NO. 2961-W