

15-135-20862-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1974  
4-19-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Inc.  
Complete Address Box 18407, Wichita, Kansas  
Lease Name Evel "E" Well No. 1  
Location C SW NE Sec. 13 Twp. 16 Rge. (E) (W) 26  
County Ness Total Depth 4555'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Strata Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 2:45 P. Day 17 Month 4 Year 1974

The above well was plugged as follows:

RTD 4555' 8 5/8 csg set at 325' cwc 200 sk. Cem. Mat. 50-50 poz W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/23/74  
INV. NO. 8970-W

Signed: Leo J. Masney  
Well Plugging Supervisor