

15-135-26892-0000

Form CP-3
Rev. 6-4-68

~~KANSAS~~

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1974
6-12-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson
Complete Address 408 One Twenty Bldg., Wichita, Kansas
Lease Name Glaves "B" Well No. 2
Location NW SW SW Sec. 11 Twp. 16 Rge. (E) (W) 26
County Ness Total Depth 4556'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 5 P Day 9 Month 6 Year 1974

The above well was plugged as follows:

RTD 4556' 8 5/8 csg set at 278' cwc 185 sk. Cmt. Mat. 50-50 poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Mansur
Well Plugging Supervisor

DATE 6/12/74
INV. NO. 9298-W