

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
SEP 19 1973  
9-19-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company.

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Ford Well No. 1

Location NE SW SE Sec. 11 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4550'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Strata Drilling Co.

Address Wichita, Kansas License No.       

Operation Completed: Hour 4:30 A Day 18 Month 9 Year 1973

The above well was plugged as follows:

RTD 4550' 8 5/8 csg set at 340' cwc 200sk. Cmt. Mat. "Halib-Light"

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 9-19-73

INV. NO. 7925-12