

15-077-19026-00-86

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1964

05-21-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas

Lease Name Eisler Well No. # 1

Location C NE NE Sec. 24 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4406

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 20th Month May Year 1964

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated. 4406' of 5 1/2" long string,
cemented to a temperature survey of 4200'. Top perferation 4275'. Perfer-
ations have been squeezed by Phillips. Hole was filled with mud to 255',
with 10' of rock bridge, and cemented with 25 sacks. Hole was filled
with mud to 40', with 10' of rock bridge, and cemented with 10 sacks
to base of the cellar.

4197' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/21/64
INV. NO. 9195-W