

15-077-30011-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1966
03-14-1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Yoder Well No. # 1

Location SE NW Sec. 19 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4412'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1:00 PM Day 8th Month March Year 1966

The Above well was plugged as follows:

265' of 8 5/8" surface pipe, cement circulated. 4412' of 4 1/2" long string,
cemented with 75 sacks. Plug back TD 4335'. Top perferation 3997'. Bottom
of the hole was sanded to 3975', and cemented with 3 sacks, through the
dump bailer. Fluid in the hole was bailed down to 260', bridge plug and
rock bridge from 260' to 250', and cemented with 25 sacks. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks
to the base of the cellar.

3603' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging Supervisor

DATE 3/14/66

INV..NO. 2856-W