

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 077-20187-00-00 (of this well)

Operator's Full Name Raymond Oil Co.

Complete Address 1 Main Pl., Suite 900, Wichita, Ks. 67202

Lease Name Smith Well No. 1

Location NW SE NE Sec. 19 Twp. 31S Rge. 7 (E) (W) X

County Harper Total Depth 4781

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12 N. Day 11 Month 9 Year 1980

The above well was plugged as follows:

240' 8 5/8" casing. 4 1/2" casing set at 4779' w/225 sax cement. Pref.,
at 4377 1/2 to 82 1/2'-Allied mixed & pumped in 4 1/2" casing 35 sax common
cement to 4250'-Pull 3395' casing-Allied mixed & pumped 8 sax hulls
25 sax gel-100 sax 50/50 posmix cement w/4% gel & 3% cc to top of
casing. Shut in w/500# pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

9-18-80

INV. NO.

3169w

Signed: 

Well Plugging Supervisor
STATE CORPORATION COMMISSION

SEP 18 1980
09-18-1980
CONSERVATION DIVISION
Wichita, Kansas