

15-077-00274-00-00

Form CP-3
Rev. 6-26-62

K
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAY 18 1964
05-18-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Robinowitz Oil Company

Complete Address: 1322 East 50th St., Tulsa, Oklahoma

Lease Name Ingle Well No. # 1

Location NE NW NE Sec. 32 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4740

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sholom Drilling Co., Inc.

Address: 1121 Union National Bldg., Wichita, Kans. License No.

Operation Completed: Hour 11:15PM Day 14th Month May Year 1964

The Above well was plugged as follows:

168' of 8 5/8" surface pipe, cemented with 150 sacks. Hole was filled with
drilling mud to 240', 1st cementing plug, bridged solid with wood and hulls,
at 240', and cemented with 40 sacks, bringing the top of the cement to 160'
in the surface pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls at 40', and cemented with 10 sacks to base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/18/64

INV. NO. 9158-W

Signed: Archie Elving
Well Plugging Supervisor