

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate well correctly on above  
Section Plat

Harper County, Sec. 24 Twp. 32 Rge. 5 (H) (W)  
Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner R. W. Rine Drilling Company, etal  
Lease Name Schon Well No. 1  
Office Address 320 Central Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-14 1954  
Application for plugging filed 12-14 1954  
Application for plugging approved 12-14 1954  
Plugging commenced 12-14 1954  
Plugging completed 12-14 1954  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes M. A. Rives, Box 8, Pratt, Kansas

Name of Conservation Agent who supervised plugging of this well " " "  
Producing formation None Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS |         |      |    |       | CASING RECORD |            |
|---------------------------|---------|------|----|-------|---------------|------------|
| FORMATION                 | CONTENT | FROM | TO | SIZE  | PUT IN        | PULLED OUT |
|                           |         |      |    | 8-5/8 | 292           | None       |
|                           |         |      |    |       |               |            |
|                           |         |      |    |       |               |            |
|                           |         |      |    |       |               |            |
|                           |         |      |    |       |               |            |
|                           |         |      |    |       |               |            |
|                           |         |      |    |       |               |            |
|                           |         |      |    |       |               |            |
|                           |         |      |    |       |               |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wood plug set @ 280', dumped 20 sacks cement, filled hole to 40' with heavy mud -  
Wood plug @ 40' - filled to surface with cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R. W. Rine Drilling Company  
Address 320 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
J. H. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) [Signature]  
320 Central Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 1954  
My commission expires July 31, 1957  
[Signature] Notary Public.

PLUGGING  
FILE SEC 24 T 32 R 5N  
BOOK PAGE 95 LINE 4

12-22-1954

R. W. Rine Drilling Co.,  
Schon Well # 1  
Total Depth  
Comm.  
Comp.  
Contractor R. C. Patton Co.,

4935  
11/19/54  
12/14/54

15-077-00136-00-00  
Location; NE, SE, NW; Section 24-T32S-  
R5W, Harper County, Kansas.  
CASING RECORD.  
8 5/8" Casing at 292 Ft.  
Cemented with 250 Sacks Cement.

|                     |      |
|---------------------|------|
| Red Bed             | 400  |
| Shale & Shells      | 825  |
| Anhydrite           | 975  |
| Lime & Shale        | 2900 |
| Sandy Shale         | 2972 |
| Sandy Lime          | 3035 |
| Lime                | 3100 |
| Sandy Shale         | 3193 |
| Lime & Shale        | 3273 |
| Shale, Sand & Lime  | 3390 |
| Lime & Shale        | 3597 |
| Lime                | 3646 |
| Lime & Shale        | 4033 |
| Lime                | 4073 |
| Lime & Shale        | 4283 |
| Lime Cherty         | 4408 |
| Cherty Lime & Shale | 4460 |
| Lime                | 4613 |
| Lime & Shale        | 4708 |
| Shale               | 4725 |
| Sand Hard           | 4784 |
| Sand Chert          | 4791 |
| Sand Chert Shale    | 4807 |
| Lime, Sand & Shale  | 4833 |
| Sand                | 4857 |
| Lime Chert          | 4865 |
| Sahle               | 4889 |
| Lime                | 4935 |
| Total Depth         | 4935 |

STATE OF Kansas COUNTY OF Lidgwick ss.

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.


R. C. PATTON CO.,

By Robert W. Patton

Subscribed and sworn to before me this 20th day of December 1954.

R. C. Hendrich  
Notary Public.

My Commission Expires Oct 4th, 1956



RE  
STATE CO. 12-22-1954  
DE 22 1954  
GONZALEZ, DONALD A. 106  
Wichita, Kansas