

15-077-00288-00-000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 25 Twp. 31S Rge. 7 W (W) (W)

Location as "NE/CNWxSWx" or footage from lines C/ SW SE
Lease Owner Olympic Petroleum Company
Lease Name Shepherd Well No. 1
Office Address 204 Columbia Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed ~~XXXXXXXXXX~~ September 3, 19 63
Application for plugging filed September 3, 19 63
Application for plugging approved September 3, 19 63
Plugging commenced September 3, 19 63
Plugging completed September 3, 19 63
Reason for abandonment of well or producing formation D & A
Rotary Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation None Depth to top Bottom Total Depth of Well 4728 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/ 60 viscosity mud to 220 feet. Set a dry hole plug added 1/2 sx hulls and 20 sx cement. Filled hole w/ 60 viscosity mud to 30 feet, set plug, added 1/4 sx hulls and 8 sx cement.
Capped rathole w/ 2 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1963
09-11-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PRIME DRILLING COMPANY
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. J. Clampitt (Agent) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 19 63

My commission expires January 17, 1967

[Signature]
Jeannine Herrman Notary Public.



15-077-00288-00-00

ROTARY DRILLING LOG

OWNER: Olympic Petroleum Company CASING: Set 8 5/8" surface
CONTRACTOR: Prime Drilling Company casing @ 219', 175 sx
LEASE: Shepard #1 HAS Pozmix
LOCATION: C SW SE Section 25-31S-7W
Harper County, Kansas

0 - 50	Sand
50 - 55	Shale
55 - 220	Shale & Shells
220 - 810	Red Bed & Shale
810 - 1115	Shale & Shells
1115 - 1225	Lime & Shale
1225 - 1505	Lime
1505 - 1538	Shale & Lime
1538 - 1648	Lime
1648 - 1807	Shale & Lime
1807 - 2087	Lime
2087 - 2175	Shale, Lime & Shells
2175 - 2490	Shale & Lime Streaks
2490 - 2735	Lime & Shale
2735 - 2777	Shale
2777 - 2794	Lime & Shale
2794 - 2814	Shale
2814 - 2840	Lime
2840 - 2985	Lime & Shale
2985 - 3375	Shale & Lime
3375 - 3529	Lime & Shale
3529 - 3530	Shale & Lime
3530 - 3590	Sand
3590 - 3752	Lime & Shale
3752 - 4103	Lime
4103 - 4270	Shale & Lime
4270 - 4346	Lime
4346 - 4428	Mississippi Chat
4428 - 4544	Mississippi Lime
4544 - 4581	Lime & Shale
4581 - 4708	Shale & Lime
4708 - 4728	Simpson Sand
4728	Rotary Total Depth

D & A

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1963
09-11-1963
CONSERVATION DIVISION
Wichita, Kansas

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

BY 
L. J. Clampitt