

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

		X	

Locate well correctly on above  
Section Plat

Harper County. Sec. 32 Twp. 38 Rge. (E) 7 (W)  
Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner Robinowitz Oil Co.  
Lease Name Ingle Well No. 1  
Office Address 1322 E. 50th St., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 5/15/64 19  
Application for plugging filed 5:30 PM 5/11/64 19  
Application for plugging approved 5:30 PM 5/11/64 19  
Plugging commenced 5:30 P M 5/11/64 19  
Plugging completed 11:15 P M 5/11/64 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Mr. Elving  
Producing formation none Depth to top Bottom Total Depth of Well 4740 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City	Water & Barren	3794	4220	8 5/8	168'	None
Mississippi	Water	4337	4584			
Simpson	Water	4694	4740			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 240' Plug of 40 sax cement  
Mud to 40' Plug of 10 sax cement  
25 sax cement in rathole

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 1964  
06-01-1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rotary Hole: Shalom Drilling Company, Inc.  
Address 6045 Pine Tree Drive, Miami Beach, Fla.

STATE OF Florida COUNTY OF Dade ss.  
MRS. Joseph Terchman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mrs. Joseph Terchman

(Address)

SUBSCRIBED AND SWORN to before me this 26 day of May, 1964

NOTARY PUBLIC STATE OF FLORIDA at-LARGE  
My commission expires MY COMMISSION EXPIRES OCT. 25, 1967

Notary Public.

SHOLOM DRILLING COMPANY, INC.  
8045 Pine Tree Drive  
Miami Beach, Florida 33140

COMPANY: Rebinowitz Oil Company  
FARM: #1 INGLE  
LOCATION: NE NW NE Sec 32 T31S R7W - Harper County, Kansas  
ROTARY DRILLING CONTRACTOR: Sholom Drilling Company, Inc.

COMMENCED: 4/30/64  
COMPLETED: 5/14/64  
I. P.: D & A

Elevation: 1478' KB  
Rotary TD: 4740'

Casing Record:

8 5/8" @ 165' 15/150 sax

LOG

0 - 35 Clay & Sand  
35 - 230 Red Bed  
230 - 1100 Red Bed & Shale  
1100 - 1215 Shale & Shell  
1215 - 1270 Anhydrite  
1270 - 1550 Gyp & Shale & Lime  
1550 - 2895 Shale & Lime  
2895 - 3050 Lime  
3050 - 3285 Lime & Shale  
3285 - 3415 Lime  
3415 - 3815 Lime & Shale  
3815 - 4072 Lime  
4072 - 4258 Lime & Shale  
4258 - 4381 Lime  
4381 - 4505 Lime & Chert  
4505 - 4554 Lime  
4554 - 4577 Chert & Lime  
4577 - 4700 Lime & Shale  
4700 - 4740 Sand & Dolomite  
4740 T. D.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 1964

06-01-1964  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF FLORIDA )  
COUNTY OF DADE ) ss.

I, Dorothy Teichman, Secretary of Sholom Drilling Company, Inc., a corporation of the State of Oklahoma, domesticated in the State of Kansas, being first duly sworn under oath, says: That I have knowledge of the facts, statements, and matters herein contained of the above described well as filed and that the same are true and correct.

Dorothy Teichman  
Dorothy Teichman

Subscribed and sworn to before me this 25th day of May, 1964.

Edythe A. Redman  
Notary Public

My commission expires:

NOTARY PUBLIC STATE of FLORIDA at LARGE  
MY COMMISSION EXPIRES OCT. 25, 1967